

ALEXANDER COUNTY HEALTH DEPARTMENT

Call 704-632-9704 between 8:00 - 9:00 AM, Mon-Fri

322 1st Avenue SW, Taylorsville, NC 28681

Improvement Permit and Operation Permit

(Ground Absorption Sewage Disposal System-Article 11 of Chapter 130A 15A NCAC 18A. 1900)

Owner Perry White Date 5/31/00Site 1000 GAL SIB NO. 160Location Highway 90 W @ All Hearts Sprinkles Ro. - Go Pass Above HouseAnd 2 houses on 1 will be Diet Room Bank UP Hill on 1 Farm where houseSubdivision Basement Yes ☐ No ☒ Lot No. 4.76 AcresBasement Plumbing Yes ☐ No ☐

HOUSE MOBILE HOME BUSINESS

Living Units 1 No. Bedrooms 1 No. Baths 1Garb. Disp. Unit yes (no)

SEPTIC TANKS SYSTEM

Size of Tank 1000 GAL SIB No. 160Installed by Louise BowmanNitrification Field 450 Sq. Ft.Number of Lines 2Length & Width of Lines: (2) 75' x 3'A. Trench System ☒ Bed System ☐Conditions M10 32 TONS #5 STONEM10 15" STONE 2 LADDSM10 18" NATURAL COVER2 BOXESWater Supply: Spring Well OtherSlope (%) 8%Soil Texture (12-36 in.) CLAYEYSoil Structure (12-36 in.) SILTSoil Depth (in.) 48"Restrictive Horizons (in.) (Imperious Strata, Rock) MIXED TRANSDITIONSoil Drainage/Ground Water (External & Internal) SAME TO ROADSoil Permeability (Application Rate) .4Site Classification P.S.

I have read and fully understand the above.

☒ Improvement Permit☐ Repair Permit☐ Authorization of☒ Existing System☐ Authorization for☐ Waste Water☐ System ConstructionOwner Perry White

IMPROVEMENT PERMIT

By John CoughlinDate 5/31/00BY John CoughlinDATE 5/31/00

The issuance of this permit does not preclude the Permittee from

complying with any and all statutes, rules, regulations, or

ordinances which may be imposed by other government agencies

(local, state, and federal) which have jurisdiction.

Crawl space shall not contain a vertical cut 24" or more.

See attached diagrams for installation specifications.

Septic tank contractor shall call prior to installation of septic

system Monday through Friday 8-9 am.

The applicant, owner, builder shall be responsible for plumbing

the home to ensure that a gravity septic system can be installed.

The septic tank shall not be installed deeper than 6" below the

surface of the natural ground level, or a pump shall be installed.

Surface diversions and/or interceptor drains may be required in

the future.

Sewage system shall be installed as drawn.

Nitrification fields and repair areas shall not be located under

paved areas or areas subject to vehicular traffic.

Well shall be located a minimum of 100' from any designated

septic area in accordance with Rules .1950 and .1956(b)

3748

AUTHORIZATION FOR WASTE WATER SYSTEM CONSTRUCTION

BY John CoughlinDATE 5/31/00

The issuance of this permit does not preclude the Permittee from

complying with any and all statutes, rules, regulations, or

ordinances which may be imposed by other government agencies

(local, state, and federal) which have jurisdiction.

Crawl space shall not contain a vertical cut 24" or more.

See attached diagrams for installation specifications.

Septic tank contractor shall call prior to installation of septic

system Monday through Friday 8-9 am.

The applicant, owner, builder shall be responsible for plumbing

the home to ensure that a gravity septic system can be installed.

The septic tank shall not be installed deeper than 6" below the

surface of the natural ground level, or a pump shall be installed.

Surface diversions and/or interceptor drains may be required in

the future.

Sewage system shall be installed as drawn.

Nitrification fields and repair areas shall not be located under

paved areas or areas subject to vehicular traffic.

Well shall be located a minimum of 100' from any designated

septic area in accordance with Rules .1950 and .1956(b)

I have read and fully understand the above.

SIGN John Coughlin DATE 5/31/00

(Owner or Authorized Agent)

OPERATION PERMIT

BY John Coughlin DATE 5/31/00

Authorization of Existing System

DATE 5/31/00

ALEXANDER COUNTY ENVIRONMENTAL HEALTH

Phone: (828)632-9704 Fax: (828)632-9008

IMPROVEMENT PERMIT DIAGRAM

44.76 TOTAL ACRES

Issued Permit # 374B

Date: 5/31/00

Owner: PERRY WHITE

EHS: SCOTT CARPENTER

Operation Permit Completed on: 6/15/00

EHS: Scott Carpenter

