

HENDERSON COUNTY DEPARTMENT OF PUBLIC HEALTH
IMPROVEMENTS PERMIT ☒ AUTHORIZATION TO CONSTRUCT ☒
FOR INSTALLATION INSPECTION CALL 694-6043 BETWEEN 7AM-8AM

22070101574

Permit Number

Owner RUSSELL NIXON Date 4-25-22

Property Address N. RUNNING DEER TRL.

Development HOMESTEAD @ MILLS RIVER Lot No. 85-R

Location: 191 TR 280 TR S. MILLS

RIVER RD. TR WHITAKER LN. TR MILLS

RIVER WAY TR BLUE MTN. WAY TR

N. RUNNING DEER TRL. TO LOT ON (R).

Residence ☒ Mobile Home ☐ Business ☐

Other ☐

Bedrooms 3

No. Employees 0 Design Flow GPD 360

Lot Size 2.35

Basement: Yes ☒ No ☐ Basement Plumbing: Yes ☒ No ☐

Water Supply: City ☐ Individual ☒ Shared ☐ Community ☐

Other ☐ WI# NOT APPLIED

Owner's Signature Emaded to Apprrecat

****VALID ONLY FOR USE AS DESCRIBED ABOVE—DRAWING NOT TO SCALE**

☒ SYSTEM TO BE INSTALLED FIRST YES ☐ SAPROLITE SYSTEM NO ☒ SEE ATTACHED INSTALLATION GUIDELINES

Associated Permits

New Construction ☒ Repair ☐

Pre-Existing Tank ☐ Addition ☐

LTAR 0.40

System Classification III 3 (INITIAL, REPAIR)

System Type 25% RED.

Linear Footage 225' x 3'

Min. Tank Size 1000 gallons

Drainfield Sq. Ft.

Max. Trench Bottom Depth on Low

Side of Trench 18"

Permit valid for 5 years from date of

issuance.

Repairs to be completed within

30 days.

Contlin

Environmental Health Specialist


The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

See attached site sketch and guidelines

***Install system according to all NC Laws and Rules for Sewage Treatment and Disposal (15A NCAC 18A .1900).**

***All Property Lines/Easements/Right-of-Ways near proposed septic area must be marked clearly prior to installation.**

***Please call if questions.**



- * INSTALL DITCH 10' MIN.
ABOVE SYSTEM TO DIVERT
SURFACE WATER AWAY
FROM SYSTEM *

X MUST ACHIEVE PROPER
FALL TO THAW OR
A PUMP WILL BE
REQUIRED.